Sl. No.	Description	Unit
	Section I - HT Works	
	NOTE: Applicable for all sections	
a	Whether explicitly mentioned under each item or not, technical / general specification accompanying Bill of quantities (BOQ) shall be followed for both material description as well as for the method of installation / execution.	
b	All the items of work shall be treated as supply, installation, testing and commissioning unless otherwise mentioned.	
c	In case of any discrepancy between the technical specifications, drawings or the BOQ, BOQ shall prevail.	
d	In case of lack of sufficient description either for the material or for the installation, description in BIS shall prevail.	
e	Only resin cast C.T of suitable burden, class accuracy, ratio and voltage shall be used.	
f	Wherever cables are laid indoor, rate for laying shall exclude cost of cable tray, humepipe etc.	
g	Wherever cables are laid outdoor, rate for laying shall include cost of excavation, laying, sand cushion, tile protection etc., as per specification.	
h	Unless otherwise explicitly mentioned, all HT cables shall be of 11kV grade, armoured, aluminium conductor and XLPE construction.	

I	The owner reserves the right to supply free of cost at site any of the equipment mentioned below. Contractor shall receive such equipment and carry out the installation.	
j	Refer schematic diagram	
k	During execution it is the responsibility of the contractror to make good to the satisfaction of the project manager of any wall chasing etc.	
l	Contractor to prepare shop drawings based on GFC drawing and to get approval before execution.	
1.0	**RING MAIN UNIT**	
	Supply, Erection, Testing and Commissioning of outdoor cubicle comprising of two loop in 11 kV, 800/630Amps 350MVA Load Break Switch as Incomer & Three loop out 11 kV, 630A VCB as Outgoings(2OD + 3VL) Which are manually operated type. The panel shall be suitable for expansion on either side and shall be coupled to the RMU. The RMU shall in all respects fulfil the requirements of BESCOM NON DAS TYPE at no extra cost to the owner. The Panel shall be made out of 14G MS sheet & shall confirm to IP54 classification the unit should be mounted on PCC pedestral.	Set
2.0	**SINGLE POLE GOS STRUCTURE**	
	Supply,installation,testing and commissioning of out door prefabricated single pole structure conforming to CESE /CEIG norms and comprising of 11 mts. concrete pole, 2 set of 3nos.group operating switch-200A,11 KV with op.handles, sets of 11 KV station type lightning arresters,"H" frames, rabbit conductor jumpers with alkathene insulation, pin /strain /disc /insulators,angles /channels / hard wares, etc. The rate shall include concrete foundations in 1:2:4 grade for pole, earthing of lightning arresters/ pole structures by using 25 x 6 mm hot dip galvonised strips to complete. Cost shall include suitable size ACSR conductors to be over head (approximately-8 running mts.) between poles if installed with in the same yard with required disc / pin / insulators as per site condition to complete.	Set

4.0	**TRANSFORMERS**	
a	250 kVA , 11/433 - Oil type Transformer without OLTC RTCC, Al. wound.(MAKE - CHETAN)	Nos.
5.0	**L.T KIOSK**	
a	Supply, erection, testing and commissioning of outdoor type LT Kiosk as per specification and Schematic Distribuiton Diagram - But non avaliablity of details Considered 1 No 400A MCCB as in Commer, 2Nos of 250A MCCB as out going, with provision for Master Meter with indicators	Nos.
	Section I - TOTAL OF HT WORKS	
6.0	**Section II - LT Switchgear & Distribution Boards**	
5.1	EB - 12 Way Feedeer Pillar Box (Out Door) - 2Nos 250A MCCB as incommer , 12 Nos of 40A 4pole MCB	Nos.
5.1	DG - 12 Way Feedeer Pillar Box (Out Door) - 2Nos 250A MCCB as incommer , 12 Nos of 40A 4pole MCB	Nos.
5.2	Common Area Panel / DG Changeover with Meter Provision (Pls Refer the Updated Scheme) Outdoor	Nos.
5.3	External Lighting Panel - 01 (Outdoor)	Nos.
5.4	External Lighting Panel - 02 (Timer Based Outdoor)	Nos.
5.5	Park-01 Outdoor Panel	Nos.
5.6	Park-02 Outdoor Panel	Nos.
5.7	DG Distribution Panel	Nos.
8.1	**Earth Electrodes**	

a	Pipe Earth Electrode using 38 mm dia class B GI pipe (3M)complete as per IS 3043 with salt, charcoal, brick masonary chamber with heavy duty RCC cover of 450mm x 450mm x 3mm chamber vide details provided in earthing scheme.	Nos.
b	Plate Earth Electrode using 19 mm dia Class B GI pipe (2.5M) and copper plate of size 600 x 600 x 3 mm thick Chamber vide details provided in earthing scheme.	Nos.
8.2	**Earth Strips**	
a	40 x 6 mm GI strip	Rmt
b	25 x 6 mm GI strip	Rmt
c	25 x 3 mm GI. strip	Rmt
d	25 x 6 mm CU strip with Sleeve	Rmt
	Section IV - Total Earth Electrodes and earth strips.	
9.0	**Section V - Miscellaneous items.**	
a	Fencing the transformer and metering yard, 2.5 meter height vide materials lised under :	
	The rates quoated shall include necessary excavation, PCC for ISMB supports, coping etc., complete.	
	Frame size : 2.5M x 1.5 M	
	M.S Angle : 50 x 6 mm	
	Chain Link : 8 SWG GI.	
	Supporting ISMB : 75 x 40 mm	
	Paint : 2 Coats of Red oxide & 2 coats of enamel paint	Rmt
b	Gate for HT Yard:	
	Frame size : 1.0m x 2.5m	
	M.S Angle : 65 x 6mm	
	Paint: Two coats of red oxide and two coats of enamel paint	Nos.

c	Spreading of 40mm thick gravel, 80mm depth in outdoor H.T yard	Sq.m
	Section - V Total Miscellaneous items.	
	TOTAL AMOUNT -	
	TOTAL SUPPLY & INSTALLATION	
	GST AT 18%	
	GRAND TOTAL INCLUDED IN GST	

aterial Supply

Qty	RATE		AMOUNT	
	Supply	INST	Supply	INST

1.0	825,000.00	15,000.00	825,000.00	15,000.00
0.0	145,000.00	35,000.00	-	-

			-	-	
			-	-	
1.0	575,000.00	15,000.00	575,000.00	15,000.00	
			-	-	
			-	-	
			-	-	
1.0	165,000.00	10,000.00	165,000.00	10,000.00	
			-	-	
4.0	167,000.00	5,000.00	668,000.00	20,000.00	
			-	-	
4.0	167,000.00	5,000.00	668,000.00	20,000.00	
			-	-	
1.0	120,000.00	5,000.00	120,000.00	5,000.00	
			-	-	
1.0	45,000.00	5,000.00	45,000.00	5,000.00	
			-	-	
1.0	75,000.00	5,000.00	75,000.00	5,000.00	
			-	-	
1.0			-	-	REQUIREI
			-	-	
1.0			-	-	REQUIREI
			-	-	
1.0	195,000.00	10,000.00	195,000.00	10,000.00	
			-	-	
			-	-	
			-	-	

16.00	6,000.00	1,500.00	96,000.00	24,000.00	
			-	-	
4.00	12,000.00	2,000.00	48,000.00	8,000.00	
			-	-	
			-	-	
150.00	245.00	50.00	36,750.00	7,500.00	
			-	-	
50.00	175.00	50.00	8,750.00	2,500.00	
			-	-	
50.00	145.00	50.00	7,250.00	2,500.00	
			-	-	
20.00	1,850.00	50.00	37,000.00	1,000.00	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
			-	-	
30.00	3,500.00	500.00	105,000.00	15,000.00	
			-	-	
			-	-	
			-	-	
			-	-	
2.00			-	-	Included in

			-	-	
10.00			-	-	Civil vendo
			-	-	
			-	-	
			3674750.00	**165500.00**	
				3840250.00	
				691245.00	
				4531495.00	

Ɔ SLD

Ɔ SLD

Fencing

›r scope